

AL101S Steering Gear Alarm System

Chapter 0 - Factory default

Chapter 1 - Operation of AL101S series ECR / FWD / AFT
Description of AL101S series keypad
Description of AL101S series lamp

Chapter 2 - Size of AL101S series ECR / FWD / AFT

Chapter 3 –Input & Output signal terminal of AL101S ECR / FWD / AFT

Chapter 4 – Test flow chart of AL101S

Chapter 0

Factory Default

1. ECR

1.1 Dip Switch

Switch	ON	OFF	Default
1	Operation Mode	Test Mode	ON
2	No DC blinking	DC blinking Available	ON
3	Full Relay output Mode	Half relay output Mode	ON
4	-	-	-
5	-	-	-
6	Operation Mode	Download Mode	ON

1.2 Resistor Termination ON/OFF switch: OFF

2. FWD / AFT

1.1 Dip Switch

Switch	ON	OFF	Default
1	Operation Mode	Test Mode	ON
2	No DC blinking	DC blinking Available	ON
3	Full Relay output Mode	Half relay output Mode	ON
4	-	-	-
5	-	-	-
6	Operation Mode	Download Mode	ON

1.2 Resistor Termination ON/OFF switch: OFF

CAUTION!


ECR / FWD / AFT Relay output mode(Full / Half) run independently.

AL101S Steering Gear Alarm System


Chapter 1

ECR / FWD / AFT Operation

AL101S-ECR









AL101S-FWD



AL101S-AFT

STEERING GEAR ALARM

PUMP 1 RUN	PUMP 1 STOP	POWER 1 FAIL	 BUZZER
PUMP 1 PHASE FAIL	PUMP 1 OVER LOAD	PUMP 1 LOW OIL LEVEL	
PUMP 1 HYDR. LOCK	FILTER 1 BLOCK		DC ON
PUMP 2 RUN	PUMP 2 STOP	POWER 2 FAIL	CONTROL POWER FAIL
PUMP 2 PHASE FAIL	PUMP 2 OVER LOAD	PUMP 2 LOW OIL LEVEL	FU FAIL
PUMP 2 HYDR. LOCK	FILTER 2 BLOCK		AUTO PILOT FAIL

SILENCE RESET LAMP TEST DIMMER

www.kingsmarine.kr Model: AL101S-AFT

www.kingsmarine.kr Model: AL101S-AFT

SILENCE RESET LAMP TEST DIMMER

1) SILENCE Key



This key able to maintain to each lamp's activation or deactivation
After buzzer has activation, this key able to stop to buzzer sound

CAUTION!

If setting Dip Switch “3” setting done ON, relay output will be working full mode.
Meanwhile if setting Dip switch “3” OFF relay output will be working half mode

2) RESET Key



This key able to re-boot to all lamp's activation and deactivation.
Press this key then press SILENCE Key again to maintain to each
lamp's activation and deactivation. Or check buzzer sound activation

3) LAMP TEST Key



This key able to all LAMP ON even each lamp has activation or deactivation
This key check to LAMP itself working.
If on pressing this key both of activation and deactivation lamp ON at once.
Then if release this key the deactivation lamp will be OFF

4) DIMMER Key



This key able to adjust to LAMP brightness
Brightness has total 5 steps.

Description of AL101S-ECR/FWD/AFT LAMP

1) **FU FAIL LAMP**

Input signal “1” second later LAMP activate

2) **PUMP HYDR. LOCK LAMP**

Input signal “1” second later LAMP activate

3) **PHASE FAIL LAMP**

Input signal “2” second later LAMP activate

4) **PUMP LOW OIL LEVEL LAMP**

Input signal “3” second later LAMP activate

5) **DC ON LAMP**

Depend on input signal LAMP will be activate to “RED” or “GREEN”
(Please see the chapter 3 Input & output signal terminal)

CAUTION!


Except above FU FAIL / **PUMP HYDR. LOCK** / PHASE FAIL /
PUMP LOW OIL LEVEL these “4” kind LAMP, the other all
LAMP will be activate once it input signal activate.

AL101S Steering Gear Alarm System


Chapter 2

ECR / FWD / AFT Case size

Cut hole dimension



Fontal case dimension




AL101S Steering Gear Alarm System


Chapter 3

ECR / FWD / AFT Input & output signal terminal


ECR input & output signal terminal



FWD input & output signal terminal



AFT input & output signal terminal



AL101S Steering Gear Alarm System

Chapter 4

Test flow

4.1 Purpose

: This alarm testing procedure is to check and confirm that the alarm system is working and meet the design requirement.

4.2 Testing Procedure

4.2.1 Connect the FWD, AFT & ECR panel as single line drawing.

4.2.2 Connect ECR panel to external alarm signals. The alarm signal can be turned off And on by a toggle switch. The signal is +24V DC. Put the switches in off position for all the alarm signals before testing.

4.3 Lamp test: Press the lamp test button, all the lamps on the panel should be on.

4.4 Dimmer test: When the lamp test button is pressed, press the dimmer button and the bright level will be change accordingly.

4.5 Individual alarms and indications test

DC ON

Step 1: Provide +24V DC at the FWD alarm panel input terminal+.

Step 2: DC ON indicator Green light is on all the panels.

Step 3: No alarm activated.

Step 4: Remove the input signal at +

Step 5: The indicator light color changes to Red and alarm activated.

Step 6: check output signal to other equipment at ECR panel when alarm activated

AUTOPILOT FAIL

Step 1: Close AUTOPILOT FAIL contact at the FWD panel input.

Step 2: Autopilot fail indicator Red light is blinking for all the panels.

Step 3: Buzzer sound.

Step 4: Press the Silence button, the autopilot fail indicator light is steady in Red and Buzzer is off.

Step 5: Press the alarm reset button, the buzzer sound again and indicator is blinking again

Step 6: Repeat Step 4.

Step 7: Cut off the AUTOPILOT FAIL contact, the autopilot fail indicator is still on

Step 8: Press alarm reset button again, the Autopilot alarm indicator light off.

Step 9: Check out signal to other equipment at ECR panel when alarm activated.

FU FAIL

Step 1: Close FU FAIL contact at the FWD panel input

Step 2: FU FAIL indicator light is blinking for all the panels.

Step 3: Buzzer sound.

Step 4: Press the silence button, the FU FAIL indicator light is steady and buzzer is off.

Step 5: Press the alarm reset button, the buzzer sound again and indication is blinking

Step 6: Repeat Step 4 .

Step 7: Cut off the FU FAIL contact, the autopilot fail indicator is still on.

Step 8: Press alarm reset button again, the alarm indicator light off

Step 9: Check out signal to other equipment at ECR panel when alarm activated

PUMP 1 RUN

- Step 1: Close PUMP 1 RUN switch
- Step 2: PUMP 1 RUN indicator light ON
- Step 3: Buzzer not on.
- Step 4: Open the PUMP 1 RUN switch
- Step 5: Indicator light off

PUMP 1 STOP

- Step 1: Close PUMP 1 STOP switch
- Step 2: PUMP 1 STOP indicator light on
- Step 3: Buzzer not on.
- Step 4: Open the PUMP 1 STOP switch
- Step 5: Indicator light off

PUMP 2 RUN & STOP

-To repeat PUMP 1 RUN & STOP test.

POWER 1 FAIL

- Step 1: Provide + 24V DC to the ECR input terminal at P4A
- Step 2: POWER 1 FAIL indicator light is blinking for all the panels.
- Step 3: Buzzer sound.
- Step 4: Press the silence button, the POWER 1 FAIL indicator light is steady and buzzer is off
- Step 5: Press the alarm reset button, the buzzer sound again and indicator is blinking again
- Step 6: Repeat Step 4.
- Step 7: Stop supply +24V DC to the terminal input, the power 1 fail indicator is still on.
- Step 8: Press alarm reset button again, the alarm indicator light off.
- Step 9: Check out signal to other equipment at ECR panel when alarm activated.

*All the other alarm testing has the same testing procedure as POWER 1 FAIL test procedure.

TIME DELAY TEST

- LOW OIL LEVEL: **3 second**
- HYDRAULC LOCK: **1 second**
- PHASE FAIL: **2 second**
- FU FAIL: **1 second**

*The testing steps are same as POWER 1 FAIL.

- Step 1: Provide alarm input signal to the respect alarm input terminal.
- Step 2: Count the time between signal input and alarm activate.
- Step 3: Compare the time between the setting an count.
- Step 4: The time delay setting and count should follow the setting time

4.6 Testing for signal output to other equipment
 FWD & AFT alarm panel relay Signal output

Input Signal	Input Location	Output Signal (FWD & AFT panels)	Output Qty Each Panel	Remark
PUMP 1 RUN	ECR	+24VDC	1	No alarm
PUMP 1 STOP	ECR	+24VDC	1	No alarm
PUMP 2 RUN	ECR	+24VDC	1	No alarm
PUMP 2 STOP	ECR	+24VDC	1	No alarm
PUMP 1 or PUMP 2 RUN	ECR	+24VDC	2	No alarm
PUMP 1 & PUMP 2 RUN	ECR	+24VDC	3	No alarm